


Irradiation Test Train Construction - Test Train Assembly Facility (TTAF)

Clifford J. Stanley
TTAF Laboratory Space Coordinator
ATR Experiment Engineering

**Advanced Test Reactor Complex
Idaho National Laboratory**



www.inl.gov



Joint Meeting:
National Organization of Test, Research, and Training Reactors
(TRTR) and the
International Group on Research Reactors (IGORR)

September 20 - 23, 2010
Knoxville, TN

(INL/CON-10-19011)


INL Test Train Assembly Facility (TTAF)

- **Location:**
 - Advanced Test Reactor (ATR) Complex
- **Purpose:**
 - Assemble Experiment Test Trains for Irradiation in the ATR
- **4300 sq ft Facility**
 - High-bay Area
 - Office Area
 - Conference Room
- **LTHC 3 Rad Facility**



Test Train Assembly Facility (TTAF)

- TTAF High-boy
 - ~ 2500 sq. ft
 - Designed and furnished with equipment to support the final assembly of variety of test train configurations
 - Staffed with experienced technicians





Test Train Assembly Welding Operation

- Automated Gas Tungsten Arc Weld (GTAW) System
- Tail Stock Driven Lath System (TDLS)
- Computer Controlled
- Typical Gas (Ar, He, or Mixture)




Detailed Machining Capabilities

- Various Materials
 - Stainless Steel
 - Aluminum
 - Graphite
 - Inconel
 - Zirconium alloys
 - Niobium
 - Hafnium
 - Copper
 - Brass





Measurement and Inspection




Assembly Quality Assurance Inspections

- Faro Laser Tracker
 - Computer based data acquisition system
 - Mirror/Tracking ball
 - 3 D location coordinates
 - 3 D modeling capability
 - Plotting (dia., length, etc.)
- Capsule and assembly straightness check
 - 0.003" over 4.5 ft
 - 0.016" over an 18 ft





Pressure and Leak Testing

- Final Test Train Assembly Integrity
- Pressure Testing (Argon)
- Leak Testing
 - Vacuum
 - Helium





Test Train Thermocouple Preparation

- Thermocouple potting
 - 2 part epoxy
- Spot welding of TC leads to TC material
- TC leads coiled inside the coiled gas flow lines (SS)
- Insert into the lead out assembly SS tube



Special Nuclear Material (SNM) Capability

- Fuel Specimens and Compacts for insertion into Test Trains
- Storage and Handling of SNM in accordance with NM Safeguards Requirements
- Category IV NM Facility



Test Capsule Assembly



Cleaning and Electroplating

- Required for induction brazing process
- Cleaning (Acid)
 - Thermocouple leads (Inconel, Niobium, SS)
 - Gas flow tubes (Inconel, Nb, SS)
 - Capsules Ultrasonic
- Plating material
 - Nickel
 - Gold



Preparation of SS Capsule End Cap and Gas Flow Tubes for Brazing





Induction Brazing Operation




Induction Brazing

- Join dissimilar metals (SS capsule, Ni leads or tubes)
- Water cooled copper coil through which the current is applied
- Brazing Material (powder)
 - Gold
 - Silver
 - Nickel
 - Copper
 - Mixtures



Experiment Gas Flow Control System

- Mockup in TTAF of the flow controls used in the ATR experiment control cubicle
 - Test valve operation
 - Test solenoid controls
- Gas flow is used for temperature control and test positioning in the core



Irradiation Capsule Assembly





Irradiation Capsule Assembly






Irradiation Capsule Assembly



Irradiation Capsule Assembly





GTAW Welding Process




Assembled Test Train – Goal Achieved !



Experiment Insertion in ATR



INL Test Train Assembly Facility (TTAF)



- Information Contacts:
- Frances Marshall
 - TTAF Lab Manager
 - ATR Experiment Program Manager
 - 208-526-8947
 - Frances.Marshall@inl.gov
- Cliff Stanley
 - TTAF Lab Space Coordinator
 - ATR Experiment Engineering
 - 208-533-4484
 - Cliff.Stanley@inl.gov